

North Marin Water District San Mateo Tank Rehabilitation Project - Novato



North Marin Water District (NMWD) has awarded a \$1.725 M contract to Farr Construction (dba Resource Development Co.) of Sparks, NV for the San Mateo Tank Rehabilitation Project. San Mateo Tank is a 5 million gallon capacity 164.5 ft diameter 34 ft high welded steel water storage tank constructed in 1966. The existing exterior coating is known to contain lead paint and will be removed in accordance with state and federal health and safety requirements. Paint removal will be abated with safety measures and testing to ensure lead contaminants do not enter the surrounding environment and are properly contained and disposed. Rehabilitation work consists of roof repairs, installing a mixing system for water quality, and modifications to bring the tank to current standards and recoating of interior and exterior of the tank.

Construction work is estimated to begin in September 2017 and be completed no later than June 2018. Work will take place between the hours of 8 a.m. and 5 p.m. Monday through Friday.