



MINIMUM SIZE CASTING REQUIRED

PIPE SIZE	6"	8"	12"	14"	16"
CASING SIZE O.D.	16"	16"	20"	24"	30"
CASING WALL	.375	.375	.375	.375	.500
SKIDS	4	4	4	6	6

NOTES:

- 1) CARRIER PIPE SHALL BE PRESSURE TESTED PRIOR TO SEALING CASING
- 2) STEEL CASING AND CARRIER PIPE SHALL INCLUDE AN ANODE PER NMWD STD. NO.12 (USE ONE TERMINAL BOX FOR ALL TEST LEADS)

PARTS LIST:

1	INSULATOR, CALPICO INC. MODEL M-12 OR EQUAL
2	WRAP AROUND END SEALS, CALPICO INC. MODEL-W OR EQUAL



WATERLINE INSTALLATION THROUGH CASING

APPROVED	DATE	REV	STD NO
	5\16\02	1	8